GYMNASIUM STORAGE

UNIT HEATER 120 V.

WALL EXHAUST 1/40 HP 120 V.

GYM

CONNECT TO EXISTING CIRCUIT 17 IN EXISTING 208/120 V. PANEL IN CLOSET ADJACENT TO LIBRARY

EXISTING CORRIDOR CEILING AND LIGHTING TO REMAIN

WALL EXHAUST 1/40 HP 120 V.

PROVIDE PLUGMOLD 2000 SURFACE METAL RACEWAY WITH RECEPTACLES MOUNTED 18" ON CENTER

UNIT HEATER 120 V.

CONNECT TO EXISTING CIRCUITS 25, 27, 29 IN EXISTING 208/120 V. PANEL IN CLOSET ADJACENT TO LIBRARY TO BE REPLACED WITH 20A-3P C/B

LIBRARY STORAGE

EXISTING DUPLEX RECEPTACLE TO BE RELOCATED AS SHOWN TO ALLOW FOR NEW DOOR INSTALLATION, RECONNECT TO EXISTING CIRCUIT.

CONNECT TO EXISTING LIGHTING CIRCUIT WHICH HAS 14 AMPS OR LESS CONNECTED LOAD IN EXISTING 277/480V. PANEL

CONNECT TO EXISTING 120/208V PANEL SPARE CIRCUIT BREAKER #9

EXISTING 277/480 V PANEL

EXISTING 208/120 V PANEL

LIBRARY

R4FP-90 1/2 HP 208V-3Ø (ON ROOF)

HVP

3#12 AND 1#12 GND 1/2"C

INLINE FAN 1/4 HP 120V.-1Ø

CONNECT TO EXISTING CIRCUIT 21 IN EXISTING 208/120V PANEL IN CLOSET ADJACENT TO LIBRARY

MATCH LINE SEE DWG. NO. E005-1

STATE PROJECT # 034-89-105-EA

DANBURY SCHOOL REORGANIZATION
CITY OF DANBURY

MILL RIDGE INTERMEDIATE

DANBURY CONNECTICUT

UNIT 'D'
ELECTRICAL PLAN

E05-3

CHECKED BY | SCALE 1/8"=1'-0" | DATE: MAY 8, 1991 | JOB NO.

Antinozzi Associates
Architects
4021 Main Street
Stratford, Connecticut

STATE OF CONNECTICUT
WILLIAM J. ROGAN
No. 7590
PROFESSIONAL ENGINEER

JANSEN & ROGAN
CONSULTING ENGINEERS, P.C.
121 WHITNEY AVENUE
NEW HAVEN, CT. 06510

KEY PLAN